





MINER ν A Module Assembly Prototyping Plan

Jaewon Park
University of Rochester

Detector Overview




Module
Assembly Unit



Mocking-up: What for?

- Develop assembly procedure, manipulation
- Possibly provides some ideas about design issues
 - Spacer between OD planes
 - H-clip (jointing ID and OD)
 - PMT Box support
- Also, Fiber routing scheme
 - fibers being bended
 - grouping to connector
 - Determines fiber lengths
- Model with light material (plywood)
 - Can't consider mechanical rigidity, weight




Things to build



- Active-target module
 - 1/3 full scale
 - 1/2 scale
 - 1/4 scale
- PMT box and support
 - 1 aluminum rack for PMT boxes
 - Many PMT boxes


Model Materials, Sizes




- Model most parts with plywood or plexiglas and glue with liquid nails
- Model fibers with fishing line

- $\frac{1}{4}$ scale (~40 in. wide)
- $\frac{1}{2}$ scale (~80 in. wide)
- $\frac{1}{3}$, full scale (~132 in. wide)



Crane in machine shop



Module Types





Fiber routing and bending



PMT Box and Support


- Model full size module for PMT box and support
- Support - aluminum bar with bolt jointing
- Fake PMT boxes – PVC pipe, hardboard, liquid nails



PMT Box Model



Hardwood dowel-rod

12"x 4" dia. PVC Pipe





Would simplify an endcap as rectangle

Might need an additional supporting block to attach dowel



Timeline



- May 9 - May 20 (2 weeks):
 - Machine Shop closed due to Machine Shop moving
- May 12
 - Some major materials (Plywood, etc) will be ordered
- May 19
 - 4 hr. Safety course with dept. machinist (Dept. requirement)
- May 23
 - Begin actual work
- 2 persons rule in machine shop
 - Work mostly daytime